Drawing Index

These sheets are a document set and should not be separated. Electrical information and references are contained on all sheets.

SITE READINESS	C1
EQUIPMENT LAYOUT (Equipment locations, heat loads, component weights	A1 s, environmental specs)
STRUCTURAL LAYOUT (Structural support/mounting locations for floor/wall,	S1 /ceiling, wall support elevations)
STRUCTURAL DETAILS (Floor and Ceiling loading information)	S2
ELECTRICAL LAYOUT (Contractor supplied wiring, interconnect methods, ju	E1 Inction point locations and descriptions)
ELECTRICAL SPECIFICATIONS (Maximum wiring run lengths, interconnect diagram,	
ELECTRICAL DETAILS	E3
EQUIPMENT DETAILS	D1

These drawings indicate the placement and interconnection of the listed equipment components. These drawings are not construction or site preparation drawings. Customer remains ultimately responsible for preparing the site to accommodate the operation of such equipment in compliance with GE Healthcare's written specifications and all applicable federal, state, and/or local requirements.

* REQUIRED REFERENCE *

Brivo CT 315/325 Pre Installation Manual

A mandatory component of this drawing set is the GE Healthcare Pre Installation manual. Failure to reference the Pre Installation manual will result in incomplete documentation required for site design and preparation.

5306512 - 1EN

Pre Installation documents for GE Healthcare products can be accessed on the web at:

www.gehealthcare.com/siteplanning

GE Healthcare

CT Site Planning



imagination at work

- prior to making changes.
- analysis, 4. Restrooms.
- containment requirements.



(GE Healthcare Site Readines	s Che	cklis	Rev 1	19
	Before using this document ensure you have the latest R GEHC Global Order # : C				0422752
	The customer is responsible for proper site preparation regardless of a	any GEHC r	neasurem	ents/inspe	ctions/assessments.
	Inspection Date: GEHC Minimum Requirements	Storage Is item ready?	PMI Is item ready?	FE Is item ready?	Comments If "N", enter comments or action plan
1	MR Magnet Delivery Requirements: Ensure cryogen venting system is available for magnet connection as defined by GEHC Pre-Installation Manual (PIM) requirements, exhaust fan system is installed and operational, 480V power, and chilled water supply is available 24x7 that meets system cooling requirements. External connectivity is available for magnet monitoring and phone service is available during delivery. Surface mount vibromat installed where required. Magnet room final flooring is in place.				
2	MR RF Screen Room Requirements: RF Screen Room is tested with copy of Test Report, emailed to ISAdminCOEMB@ge.com, that it is compliant with GEHC specifications. Dock Bolt and magnet anchors (if applicable) installed using 2 part anchor. For HDx systems, blower box mount bolts installed by RF vendor using 2 part anchors				
3	State Regulatory Requirements: Facility registration number provided for states of III, KY, HI, RI, SC, TX. X-ray shielding plan and state acknowledgment letter provided to installer for AR, DC, NC, SC, CO & WA. Site Drawing Requirements: Final version of equipment network and antenna, installation drawings (including red lined versions) verified to match actual room and has been provided to installer.				
4	Surface Penetration Requirements: Customer/Contractor scheduled to provide required drilling or cutting into floors, ceilings, and walls; OR surface penetration permit available and posted in the room when GEHC will perform the work.				
5	Pre-Delivery Route Requirements: The equipment delivery route from the truck to the final destination within the facility has been reviewed with all key stakeholders to safely meet the minimum requirements for equipment access, and all communications/notifications have occurred. Arrangements have been made for special handling (elevator, rigging, floor protection, fork lift, rollback truck, etc).				
6	Finished Room Requirements: Rooms that will contain equipment, including storage areas not in scan suite, are dust free. Provisions taken to maintain a dust free room. Precautions must be taken to prevent dust from entering rooms containing equipment when construction is incomplete in adjacent areas. All walls primed (final coat not needed on Day 1). Shielding, doors, and windows are to be installed. No contractor work being done during or after the installation that will cause dust in the installation areas or potential equipment damage. Room security to prevent unauthorized access and theft has been discussed with customer. The customer is aware of these security issues, implications and responsibility. For Storage: Room must meet PIM requirements for storage.				
7	Electrical Requirements: Lockable (LOTO) Main Disconnect Panel (MDP) is installed per GE guidelines and system power is available. Conduits, electrical cable ducting/dividers/cable trays, and access flooring is installed in proper location and height. Surface floor duct and load-side wires can be installed at time of system installation. Validate outlet location and requirements meet specifications for device/equipment.				
8	HVAC Requirements: The HVAC/Chilled Water systems designed to maintain the environment per spec/PIM is at running state and appears to provide the desired environmental conditions including location of vents, temperature and humidity for system operation.				
9	Flooring Requirements: Floor is clean and prepared for final floor covering. Floor levelness/flatness is measured and within tolerance, and there are no visible defects per GEHC specifications. Confirm customer anchoring plan aligns with designed floor thickness. Final flooring installed where required for network racks.				
10	Ceiling Requirements: Unistrut (or equivalent) location, levelness and spacing is measured (or vendor confirmed) and consistent with the requirement of the installation drawings. Ensure unistrut and rails are not used as mounting surfaces. Ceiling grid is installed. Permanent lighting is installed and operational. HVAC diffusers are installed and connected to ductwork. Ceiling tiles installed per PMI discretion.				
11	Staging Requirements: Space has been identified to support the active installation process only. This area meets PIM/project book requirements. Storage space has been identified, if needed. This secured space would be used to store equipment indefinitely. If offsite, transportation plan has been developed at customer expense. This space must meet PIM requirements.				
12	Network Connectivity: Hardwire for network connectivity(network drop) is in place prior to delivery with specified network firewall configuration where required. Site Surveys for wireless mobile XR units have been completed.				
13	Medical Gases Requirements: Systems (hard piped or portable) in place to allow testing and calibration of equipment (anesthesia), including ventilation.				

Customer Site Readiness Requirements

• Any deviation from these drawings must be communicated in writing to and reviewed by your local GE Healthcare Installation Project Manager

• Make arrangements for any rigging, special handling, or facility modifications that must be made to deliver the equipment to the installation site. If desired, your local GE Healthcare Installation Project Manager can supply a reference list of rigging contractors.


• New construction requires the following; 1. Secure area for equipment, 2. Power for drills and other test equipment, 3. Capability for image

• Provide for refuse removal and disposal (e.g. crates, cartons, packing)

• Contact a radiation physicist or consultant to specify radiation


GE Equipment Delivery Requirements

The items on the GE Healthcare Site Readiness Checklist are REQUIRED to facilitate equipment delivery to the IS site. Equipment will not be delivered if these requirements are not satisfied.




	IPM	GE EQUIPMEN 1ENT ON ORDER FROM GE HEALTHCARE, INSTAL			EQUIP	MENT CF	ROSS		SCALE: 1:50 This equipment layout indicates the pla
PER	:	NEITHER A QUOTE OR GON WAS ISSUED AT THE DATE (of these drawi	NGS	REFER	ENCE C	HART PPROVAL		of these components. It remains the
IOT BE	e: Ins	LOCAL CONDITIONS MAY DICTATE THAT ITEMS IDE STALLED BY OTHERS.	NTIFIED IN THI	S CATEGORY	SEISMIC C STATUS S	= CALCU PEND = SPECI	JLATIONS/ ING APPRO	DVAL	
M).	\int	– QUANTITY ORDERED REFER TO SHEET "D"					ELEC]	
>		ITEM DESCRIPTION (* = EXISTING/REINSTALL)	WEIGHT	HEAT OUTPUT (PER HOUR)	DETAIL NO.		PLAN		
		OPERATORS CONSOLE OPERATOR'S CHAIR	30 kg	860 W			ПС	-	
		TABLE Rear cable cover	32 kg		B8141			-	
	1	BRIVD 315/325 GANTRY	948 kg	2900 W	B8315A B8315B B8315C B8315D B8315D B8315E	-	стт	С	
	1	PATIENT TABLE WITH EXTENDED TABLE	180 kg			_			
		ADAPTER	318 kg		B8135	-	AD	s	
	TH AR	HE FOLLOWING ITEMS, WHICH HAVE BEEN (RE TO BE INSTALLED BY THE CUSTOMER (ORDERED FR DR HIS CONT	OM GE HEAL RACTOR.	THCARE,				
								\square	
			1	1	1	1	1	1	

EQUIPMENT LAYOUT	RECOMMENDED CEILING HEIGHT =
placement and interconnection of the indicated equipment components. There may be t	federal, state, and/or local requirements that could impact the
he Customer's responsibility for ensuring the site and final equipment placement complies	s with all applicable federal, state, and/or local requirements.





2438MM placement	ANCILLARY ITEMS CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEM NO. (* INDICATES EXISTING)	e - Design Center ^{Wisconsin}
	60 COUNTER TOP FOR EQUIPMENT-MINIMUM DEPTH 30 in. DR ADDITIONAL SHELVING MAY BE REQUIRED PROVIDE GROMMETED DENINGS AS REQUIRED TO ROUTE INTERCONNECT CABLES TO RACEWAY BELOW COUNTERTOP. 61 LEAD GLASS WINDOW 62 X-RAY ON WARNING LIGHT - AVAILABLE FROM GE SUPPLY CALL' 800-200-9760 GE CAT. NO. WXIABWW-OF-XIU 63 DOOR LIMIT SWITCH (REQUIRED IN SOUTH CAROLINA, OTHERWISE NEEDED ONLY IF REQUIRED BY STATE/LOCAL CODES) 64 MINIMUM DOOR OPENING FOR EQUIPMENT DELIVERY IS 44 IN. W × 83 IN. H [1118mm × 2108mm], CONTINGENT ON A 96 IN. [2438mm] CORRIDOR WIDTH	GE Healthcare Milwaukee,
	THE FOLLOWING ITEMS ARE AVAILABLE FROM GE HEALTHCARE TECHNOLOGIES. CONTACT YOUR LOCAL GE HEALTHCARE SERVICE REPRESENTATIVE FOR PRICING AND AVAILABILITY.	EQUIPMENT LAYOUT BRIVO CT315/325 TO SUGGEST LOCATION OF GE HEALTHCARE EQUIPMENT TUS, ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. A, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS CERPECTED TO BE INSTALLED. IT IS NOT TO BE USED FOR DURPOSES, HOWEVER, AND THE COMPANY CANNOT ACCEPT DAMAGES RESULTING THEREFROM.
	 GENERAL SPECIFICATIONS THE REQUIRED CEILING HEIGHT INDICATED ON THESE PLANS IS TO ENSURE EQUIPMENT FUNCTION IS NOT INHIBITED. CONSULT WITH YOUR LOCAL GEHC IS SPECIALIST REGARDING ACCEPTABILITY OF OTHER CEILING HEIGHTS. CHECK ALL DOOR OPENINGS AND HALLWAYS FROM DELIVERY LOCATION TO WHERE EQUIPMENT IS TO BE INSTALLED TO ENSURE THE ROUTE PHYSICALLY AND STRUCTURALLY WILL ACCOMODATE THE EQUIPMENT AS SHIPPED. RADIATION PROTECTION REQUIREMENTS ARE NOT INDICATED ON THIS PLAN. WHERE NEEDED PER NATIONAL OR LOCAL CODE THEY SHALL BE SPECIFIED BY A QUALIFIED RADIOLOGICAL PHYSICIST. THE DEVELOPMENT OF THE EQUIPMENT LAYOUT, ROOM DIMENSIONS, MECHANICAL AND ELECTRICAL SUGGESTIONS IS PREDICATED UPON THE BEST INFORMATION OBTAINABLE FROM THE SITE, COUPLED WITH THE CUSTOMER'S KNOWN DESIRES. ARCHITECTURAL OR ELECTRICAL SUGGESTIONS IS PREDICATED UPON THE BEST INFORMATION OBTAINABLE FROM THE SITE, COUPLED WITH NOTIFICATION OF EQUIPMENT ILLUSTRATED ON THIS DRAWING IS ALLOWED ONLY WITH NOTIFICATION, SERVICEABILITY, AND RESTRICTING CABLE LENGTHS, ETC., MAKE THIS ESSENTIAL FOR A PROPER IS. GEHC RESERVES THE RIGHT TO MAKE ON THE JOB CHANGES BECAUSE OF CUSTOMER REQUIREMENTS AND/OR OBSTACLES IN CONSTRUCTION, ETC ALL WORK TO BE IN COMPLIANCE WITH NATIONAL AND LOCAL BUILDING SAFETY CODES. 	F F DALITY TYPE: E MODALITY TYPE: E MODALITY TYPE: E AD ASSOCIATED APPARATI IN PREPARING THIS PLAN, TO ACTUAL CONSTRUCTION PLAN, TO
	 DIMENSIONS ARE TO FINISHED SURFACES OF ROOM SITE ENVIRONMENT SPECIFICATIONS AMBIENT OPERATING TEMPERATURE: 64* TO 79* F, (20* TO 28* C) MAXIMUM ALLOWABLE TEMPERATURE CHANGE OF 5* F (3* C)/HOUR, MAXIMUM ROOM TEMPERATURE GRADIENT 5*F, (5* C). HUMIDITY: 30 TO 70 PERCENT NON-CONDENSING, MAXIMUM ALLOWABLE CHANGE OF 5 PERCENT/HOUR. ALTITUDE: NOT TO EXCEED 7875 FT. (3200M) ABOVE SEA LEVEL. THE ENVIRONMENT FOR THE ELECTRONICS CABINET MUST BE CONTROLLED SO THE ABOVE RESTRICTIONS ARE NOT EXCEEDED. DO NOT RESTRICT THE AIR INTAKE OR AIR EXHAUST OF THE SYSTEM COMPONENTS. ENVIRONMENTAL CONDITIONS LISTED ABOVE MUST BE MAINTAINED AT ALL TIMES INCLUDING FOR EXAMPLE OVERNIGHT, WEEKENDS, AND HOLIDAYS. 	PROJECT ILLE: PROJECT REVISION 6-86f 03
	 AC MAGNETIC FIELDS MUST BE BELOW 0.01 GAUSS PEAK. CT COMPUTER EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN TEN GAUSS TO GUARANTEE DATA INTEGRITY. MULTIFORMAT CAMERA EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN THREE GAUSS TO OBTAIN SPECIFIED GEOMETRIC LINEARITY. CT CONSOLE EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN TEN GAUSS TO OBTAIN SPECIFIED GEOMETRIC LINEARITY. CT CONSOLE EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN TEN GAUSS TO OBTAIN SPECIFIED GEOMETRIC LINEARITY. 	DATE: 25.May.16 DRAWN BY: DMH CHECKED BY: DJP REVISION HISTORY:


	01100000			
TYPICAL WALL	SUPPORT	ELEVATIONS	SCALE: 1:50	
	:			



ITEM NO.	ITEM DESCRIPTION (* INDICATES EXISTING)	- Design Cer
1	LEVELING AREA FOR GANTRY AND TABLE SEE DETAIL B78164 ON SHEET S2.	GE Healthcare Healthcare Project Implementation -
		SHEET TITLE: STRUCTURAL LAYOUT MODALITY TYPE: BRIVO CT315/325 THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WRING DETALS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETALS TO ACTUAL EQUIPMENT EXPECTED TO BE INSTALLED. IT IS NOT TO BE USED FOR ACTUAL COUPRIENT EXPECTED TO BE INSTALLED. IT IS NOT TO BE USED FOR ACTUAL CONFIRINCIPAL HOWFVER, AND THF COMPANY CANNOT ACCFT
o M S F O A S T L O A S T L O O F iii O E	STRUCTURAL NOTES ALL STEEL WORK AND PARTS NECESSARY TO SUPPORT CEILING MOUNTED EQUIPMENT S TO BE SUPPLIED BY THE CUSTOMER OR HIS CONTRACTORS. METHODS OF SUPPORT FOR THE STEELWORK THAT WILL PERMIT ATTACHMENT TO STRUCTURAL STEEL OR THROUGH BOLTS IN CONCRETE CONSTRUCTION SHOULD BE FAVORED. DO NOT USE CONCRETE OR MASONRY ANCHORS IN DIRECT TENSION. ALL UNITS THAT ARE WALL MOUNTED OR WALL SUPPORTED ARE TO BE PROVIDED WITH SUPPORTS WHERE NECESSARY. WALL SUPPORTS ARE TO BE SUPPLIED AND INSTALLED BY THE CUSTOMER OR HIS CONTRACTORS. SEE PLAN AND DETAIL SHEETS FOR SUGGESTED .OCCATIONS AND MOUNTING HOLE LOCATIONS. ALL CEILING MOUNTED FIXTURES, AIR VENTS, SPRINKLERS, ETC. TO BE FLUSH MOUNTED, DR SHALL NOT EXTEND MORE THAN 1/4" BELOW THE FINISHED CEILING. FLOOR SLABS ON WHICH EQUIPMENT IS TO BE INSTALLED MUST BE LEVEL TO 1/4" n 10'-0" DIMENSIONS ARE TO FINISHED SURFACES OF ROOM.	PROJECT TILE: 6-86F BRIVO CT315/325
0 C 0 C F N 0 T F E V 0 T F E V 0 T F E V 1 1 1 1 1 1 1 1 1 1 1 1 1	WIRING, CONDUITS, PIPING, DUCT WORK OR STRUCTURAL SUPPORTS (I.E. POST TENSION CABLES OR REBAR)) WILL INTERFERE OR COME IN CONTACT WITH SUBSURFACE PENETRATION OPERATIONS (E.G. DRILLING AND INSTALLATION OF ANCHORS/SCREWS) PERFORMED DURING THE INSTALLATION PROCESS. TO ENSURE WORKER SAFETY, GE NSTALLERS WILL PERFORM SURFACE PENETRATION OPERATIONS ONLY AFTER THE CUSTOMER'S VALIDATION AND COMPLETION OF THE "GE SURFACE PENETRATION PERMIT"	PROJECT REVISION 6-86f 03 DATE: 25.May.10 DRAWN BY: DMI CHECKED BY: DJI REVISION HISTORY:







ELECTRICAL PLAN

RECOMMENDED CEILING HEIGHT = 2438MM

ELECTRICAL OUTLET LEGEND CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS. HEIGHT ABOVE FLOOR DETERMINED BY LOCAL CODES UNLESS OTHERWISE SPECIFIED.

- DEDICATED TELEPHONE LINE(S) (SEE ELECTRICAL Δ
- DETAIL ELEC-1 OR ELEC-67) NETWORK OUTLET (SEE ELECTRICAL DETAILS ELEC-83 AND ELEC-84 OR ELEC-87)
- CONDUIT AND DUCT RUNS SHALL HAVE SWEEP RADIUS BENDS
- CONDUITS AND DUCT ABOVE CEILING OR BELOW FINISHED FLOOR MUST BE INSTALLED AS NEAR TO CEILING OR FLOOR AS POSSIBLE TO REDUCE RUN LENGTH.


JUNCTION POINT NOTES


ALL JUNCTION BOXES, CONDUIT, DUCT, DUCT DIVIDERS, SWITCHES, CIRCUIT BREAKERS, CABLE TRAY, ETC., ARE TO


- CEILING MOUNTED JUNCTION BOXES ILLUSTRATED ON THIS PLAN MUST BE INSTALLED FLUSH WITH FINISHED CEILING. ALL DUCTWORK MUST MEET THE FOLLOWING REQUIREMENTS:
- 1. DUCTWORK SHALL BE METAL WITH DIVIDERS AND HAVE REMOVABLE, ACCESSIBLE COVERS.


BE SUPPLIED AND INSTALLED BY CUSTOMERS ELECTRICAL CONTRACTOR.


- 2. DUCTWORK SHALL BE CERTIFIED/RATED FOR ELECTRICAL POWER PURPOSES. 3. DUCTWORK SHALL BE ELECTRICALLY AND MECHANICALLY BONDED TOGETHER IN AN APPROVED MANNER.
- 4. PVC AS A SUBSTITUTE MUST BE USED IN ACCORDANCE WITH ALL LOCAL AND NATIONAL CODES.
- ALL OPENINGS IN ACCESS FLOORING ARE TO BE CUT OUT AND FINISHED OFF WITH GROMMET MATERIAL BY THE CUSTOMERS CONTRACTOR.
- GENERAL CONTRACTOR TO INSERT PULL CORDS FOR ALL CABLE RUN CONDUITS BETWEEN THE EQUIPMENT ROOM AND THE OPERATORS CONTROL ROOM. 10 FOOT PIGTAILS AT ALL JUNCTION POINTS.
- ALL WIRING MUST BE THHN OR TFFN STRANDED COPPER THERMOPLASTIC 600 VOLT OR EQUIVALENT INSULATION.
- ALUMINUM OR SOLID WIRES ARE NOT ALLOWED. GROUNDING IS CRITICAL TO EQUIPMENT FUNCTION AND PATIENT SAFETY. SITE MUST CONFORM TO WIRING SPECIFICATIONS SHOWN ON THIS PLAN.















POWER POWER



THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED

- \angle

