

# Drawing Index

These sheets are a document set and should not be separated. Electrical information and references are contained on all sheets.

SITE READINESS	C1
EQUIPMENT LAYOUT (Equipment locations, heat loads, component weights, environmental specs)	A1
STRUCTURAL LAYOUT (Structural support/mounting locations for floor/wall/ceiling, wall support elevations)	S1
STRUCTURAL DETAILS (Floor and Ceiling loading information)	S2
ELECTRICAL LAYOUT (Contractor supplied wiring, interconnect methods, junction point locations and descriptions)	E1
ELECTRICAL SPECIFICATIONS (Maximum wiring run lengths, interconnect diagram, system power specifications)	E2
ELECTRICAL DETAILS	E3
EQUIPMENT DETAILS	D1 THRU D2

These drawings indicate the placement and interconnection of the listed equipment components. These drawings are not construction or site preparation drawings. Customer remains ultimately responsible for preparing the site to accommodate the operation of such equipment in compliance with GE Healthcare's written specifications and all applicable federal, state, and/or local requirements.

**\* REQUIRED REFERENCE \***  
**Optima PET-CT**  
**560**  
**Pre Installation Manual**  
**5266541-1EN**

A mandatory component of this drawing set is the GE Healthcare Pre Installation manual. Failure to reference the Pre Installation manual will result in incomplete documentation required for site design and preparation.

Pre Installation documents for GE Healthcare products can be accessed on the web at:

[www.gehealthcare.com/siteplanning](http://www.gehealthcare.com/siteplanning)

# GE Healthcare



## PET-CT Site Planning



imagination at work

# Customer Site Readiness Requirements

- Any deviation from these drawings must be communicated in writing to and reviewed by your local GE Healthcare Installation Project Manager prior to making changes.
- Make arrangements for any rigging, special handling, or facility modifications that must be made to deliver the equipment to the installation site. If desired, your local GE Healthcare Installation Project Manager can supply a reference list of rigging contractors.
- New construction requires the following; 1. Secure area for equipment, 2. Power for drills and other test equipment, 3. Capability for image analysis, 4. Restrooms.
- Provide for refuse removal and disposal (e.g. crates, cartons, packing)
- Contact a radiation physicist or consultant to specify radiation containment requirements.

# GE Equipment Delivery Requirements

The items on the GE Healthcare Site Readiness Checklist are REQUIRED to facilitate equipment delivery to the IS site. Equipment will not be delivered if these requirements are not satisfied.

GE Healthcare Site Readiness Checklist Rev 19					
Before using this document ensure you have the latest Rev from MyWorkshop on DDC0422752					
GEHC Global Order #:		Customer:			
GEHC PMI:		FE / Installer:			
The customer is responsible for proper site preparation regardless of any GEHC measurements/inspections/assessments.					
Inspection Date:		Storage is ready?	PMI is ready?	FE is ready?	Comments
<b>GEHC Minimum Requirements</b>					
1	<b>MR Magnet Delivery Requirements:</b> Ensure oxygen venting system is available for magnet connection as defined by GEHC Pre-Installation Manual (PIM) requirements; exhaust fan system is installed and operational, 480V power, and chilled water supply is available 24x7 that meets system cooling requirements. External connectivity is available for magnet monitoring and phone service is available during delivery. Surface mount vibromat installed where required. Magnet room final flooring is in place.				
2	<b>MR RF Screen Room Requirements:</b> RF Screen Room is tested with copy of Test Report, emailed to 560min@ge.com, that is compliant with GEHC specifications. Dock bolt and magnet anchors (if applicable) installed using 2 part anchor. For HDx systems, blower box mount bolts installed by RF vendor using 2 part anchors.				
3	<b>State Regulatory Requirements:</b> Facility registration number provided for states of IL, KY, HI, RI, SC, TX. X-ray shielding plan and state acknowledgment letter provided to installer for AR, DC, NC, SC, CO & WA.				
4	<b>Site Drawing Requirements:</b> Final version of equipment network and antenna, installation drawings (including red lined versions) verified to match actual room and has been provided to installer.				
5	<b>Surface Penetration Requirements:</b> Customer/Contractor scheduled to provide required drilling or cutting into floors, ceilings, and walls, OR surface penetration permit available and posted in the room when GEHC will perform the work.				
6	<b>Pre-Delivery Route Requirements:</b> The equipment delivery route from the truck to the final destination within the facility has been reviewed with all key stakeholders to safely meet the minimum requirements for equipment access, and all communications/notifications have occurred. Arrangements have been made for special handling (elevator, rigging, floor protection, fork lift, rollback truck, etc).				
7	<b>Finished Room Requirements:</b> Rooms that will contain equipment, including storage areas not in scan suite, are dust free. Provisions taken to maintain a dust free room. Precautions must be taken to prevent dust from entering rooms containing equipment when construction is incomplete in adjacent areas. All walls primed (final coat not needed on Day 1). Shielding, doors, and windows are to be installed. No contractor work being done during or after the installation that will cause dust in the installation areas or potential equipment damage. Room security to prevent unauthorized access and theft has been discussed with customer. The customer is aware of these security issues, implications and responsibility. For Storage: Room must meet PIM requirements for storage.				
8	<b>Electrical Requirements:</b> Lockable (LOTO) Main Disconnect Panel (MDPI) is installed per GE guidelines and system power is available. Conduits, electrical cable ducting/dividers/cable trays, and access flooring is installed in proper location and height. Surface floor duct and load-side wires can be installed at time of system installation. Validate outlet location and requirements meet specifications for device/equipment.				
9	<b>HVAC Requirements:</b> The HVAC/Chilled Water systems designed to maintain the environment per spec/PIM is at running state and appears to provide the desired environmental conditions including location of vents, temperature and humidity for system operation.				
10	<b>Flooring Requirements:</b> Floor is clean and prepared for final floor covering. Floor levelness/flatness is measured and within tolerance, and there are no visible defects per GEHC specifications. Confirm customer anchoring plan aligns with designed floor thickness. Final flooring installed where required for network racks.				
11	<b>Ceiling Requirements:</b> Unistrut (or equivalent) location, levelness and spacing is measured (or vendor confirmed) and consistent with the requirement of the installation drawings. Ensure unistrut and rails are not used as mounting surfaces. Ceiling grid is installed. Permanent lighting is installed and operational. HVAC diffusers are installed and connected to ductwork. Ceiling tiles installed per PIM discretion.				
12	<b>Staging Requirements:</b> Space has been identified to support the active installation process only. This area meets PIM/project book requirements.				
13	<b>Network Connectivity:</b> Hardware for network connectivity/network drop is in place prior to delivery with specified network firewall configuration where required. Site Surveys for wireless mobile XR units have been completed.				
14	<b>Medical Gases Requirements:</b> Systems (hard piped or portable) in place to allow testing and calibration of equipment (anesthesia), including ventilation.				

**GE Healthcare**  
 Healthcare Project Implementation - Design Center  
 Milwaukee, Wisconsin  
 Copyright 2009 General Electric Company - Proprietary to GE

SHEET TITLE: **SITE READINESS**  
 MODALITY TYPE: **OPTIMA PET/CT 560**  
THIS PLAN IS SUBMITTED TO SURVEY LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS. ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE LATEST REVISED DRAWINGS AND TO THE LATEST REVISED SPECIFICATIONS. GE HEALTHCARE ACCEPTS NO LIABILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
**12-24f**  
**TYPICAL LAYOUT**

PROJECT	REVISION
12-24f	05
DATE:	06 JUN 16
DRAWN BY:	DMH
CHECKED BY:	REK

REVISION HISTORY:


SHEET  
**C1**

PIM R12  
 RQ - 161174

GE EQUIPMENT LISTING

EQUIPMENT ON ORDER FROM GE HEALTHCARE, INSTALLED BY GE HEALTHCARE, PER : NEITHER A QUOTE OR GON WAS ISSUED AT THE DATE OF THESE DRAWINGS

NOTE: LOCAL CONDITIONS MAY DICTATE THAT ITEMS IDENTIFIED IN THIS CATEGORY BE INSTALLED BY OTHERS.

EQUIPMENT CROSS REFERENCE CHART  
 P = PREAPPROVAL  
 C = CALCULATIONS/PENDING APPROVAL  
 S = SPECIFICATIONS ONLY

ITEM NO.	QUANTITY ORDERED	REFER TO SHEET "D"	ITEM DESCRIPTION (* = EXISTING/REINSTALL)	WEIGHT	HEAT OUTPUT (PER HOUR)	DETAIL NO.	STRC PLAN	ELEC PLAN
1	1		D-CORE	191 lbs	1498 btu	B56062C	-	CCDR
2	1		POWER DISTRIBUTION UNIT	813 lbs	3399 btu	P5057F	-	PDU
3	1		DISCOVERY PET/CT 610/560/560FX (16 SLICE)	8046 lbs	24740 btu	B5060A B5060C B610C B6090D B610E P5057D P5057E	-	CTPT
4	1		PATIENT TABLE W/300 LB PATIENT	2312 lbs	1023 btu		-	S
5	1		STORAGE CABINET (EMPTY CABINET WEIGHT)	99 lbs		M33005	-	-
6	1		FREEDDM WORKSPACE LARGE TABLE	123 lbs		B8143	-	S
7	1		CONSOLE CABINET WITH TWO MONITORS	211 lbs	3624 btu	B8142	-	CC
8	1		OPERATOR'S CHAIR				-	-
9	1		UPS SYSTEM	619 lbs	5122 btu	B7864PZ	-	UPS

THE FOLLOWING ITEMS, WHICH HAVE BEEN ORDERED FROM GE HEALTHCARE, ARE TO BE INSTALLED BY THE CUSTOMER OR HIS CONTRACTOR.

SCALE: 1/4" = 1'-0"

EQUIPMENT LAYOUT


RECOMMENDED CEILING HEIGHT = 9'-0"

This equipment layout indicates the placement and interconnection of the indicated equipment components. There may be federal, state, and/or local requirements that could impact the placement of these components. It remains the Customer's responsibility for ensuring the site and final equipment placement complies with all applicable federal, state, and/or local requirements.

IMPORTANT CUSTOMER READINESS ALERT:

THIS EQUIPMENT INVOLVES THE USE OF RADIOACTIVE ISOTOPES, INCLUDING THOSE SOURCES NECESSARY FOR EQUIPMENT CALIBRATION. APPROPRIATE REGULATORY COMPLIANCE AND LICENSING MUST BE ARRANGED BY THE CUSTOMER EARLY IN THE PLANNING PROCESS AND THEN DEMONSTRATED/AVAILABLE FOR EQUIPMENT INSTALLATION.

NOTE: DELIVERY PATH DOWN CORRIDORS FOR GANTRY'S AND TABLE MUST BE EVALUATED PRIOR TO CONSTRUCTION, AS 90 DEGREE TURNS REQUIRE SPECIFIC CORRIDOR WIDTH.



ANCILLARY ITEMS

CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS

ITEM NO.	ITEM DESCRIPTION (* INDICATES EXISTING)
60	X-RAY ON WARNING LIGHT - AVAILABLE FROM GE SUPPLY CALL: 800-200-9760 GE CAT. NO. WX1ABW-DF-XIU
61	MINIMUM DOOR OPENING FOR EQUIPMENT DELIVERY IS 48 IN. W X 82 IN. H (1267mm X 2083mm). CONTINGENT ON A 71 IN. (1803mm) CORRIDOR WIDTH
62	DOOR LIMIT SWITCH (REQUIRED IN SOUTH CAROLINA, OTHERWISE NEEDED ONLY IF REQUIRED BY STATE/LOCAL CODES)
63	COUNTER TOP FOR EQUIPMENT-MINIMUM DEPTH 24 IN. OR ADDITIONAL SHELVING MAY BE REQUIRED TO PROVIDE CREWMEMBER OPENINGS AS REQUIRED TO ROUTE INTERCONNECT CABLES TO RACEWAY BELOW COUNTERTOP.
64	LEAD GLASS WINDOW

THE FOLLOWING ITEMS ARE AVAILABLE FROM GE HEALTHCARE TECHNOLOGIES. CONTACT YOUR LOCAL GE HEALTHCARE SERVICE REPRESENTATIVE FOR PRICING AND AVAILABILITY.

90	E4502RL WARNING LIGHT CONTROL OR EQUIVALENT MAX 24V CONTROLLER.
91	MAIN DISCONNECT CONTROL GEMS CAT. NO. E4502AB 90 IN. SEE DETAIL E4502AD. (IF A UPS IS NOT OR WILL NOT BE ORDERED, THE E4502AD CAN BE USED.)

GENERAL SPECIFICATIONS

- THE REQUIRED CEILING HEIGHT INDICATED ON THESE PLANS IS TO ENSURE EQUIPMENT FUNCTION IS NOT INHIBITED. CONSULT WITH YOUR LOCAL GEHC SPECIALIST REGARDING ACCEPTABILITY OF OTHER CEILING HEIGHTS.
- CHECK ALL DOOR OPENINGS AND HALLWAYS FROM DELIVERY LOCATION TO WHERE EQUIPMENT IS TO BE INSTALLED TO ENSURE THE ROUTE PHYSICALLY AND STRUCTURALLY WILL ACCOMMODATE THE EQUIPMENT AS SHIPPED.
- RADIATION PROTECTION REQUIREMENTS ARE NOT INDICATED ON THIS PLAN. WHERE NEEDED PER NATIONAL OR LOCAL CODE THEY SHALL BE SPECIFIED BY A QUALIFIED RADIOLOGICAL PHYSICIST.
- THE DEVELOPMENT OF THE EQUIPMENT LAYOUT, ROOM DIMENSIONS, MECHANICAL AND ELECTRICAL SUGGESTIONS IS PREDICATED UPON THE BEST INFORMATION OBTAINABLE FROM THE SITE, COUPLED WITH THE CUSTOMER'S KNOWN DESIRES. ARCHITECTURAL OR ELECTRICAL CHANGES INCLUDING RELOCATION OF EQUIPMENT ILLUSTRATED ON THIS DRAWING IS ALLOWED ONLY WITH NOTIFICATION, IN WRITING, AND REVIEW BY GEHC SERVICE DEPARTMENT. EQUIPMENT OPERATION, SERVICEABILITY, AND RESTRICTING CABLE LENGTHS, ETC., MAKE THIS ESSENTIAL FOR A PROPER IS. GEHC RESERVES THE RIGHT TO MAKE ON THE JOB CHANGES BECAUSE OF CUSTOMER REQUIREMENTS AND/OR OBSTACLES IN CONSTRUCTION, ETC..
- ALL WORK TO BE IN COMPLIANCE WITH NATIONAL AND LOCAL BUILDING SAFETY CODES.
- DIMENSIONS ARE TO FINISHED SURFACES OF ROOM

SITE ENVIRONMENT SPECIFICATIONS

- AMBIENT OPERATING TEMPERATURE: 64° F TO 79° F, (18° C TO 26° C)
- HUMIDITY: 30 TO 60 PERCENT NON-CONDENSING, STATIC CHARGES ASSOCIATED WITH LOWER HUMIDITY LEVELS MAY INTERFERE WITH SYSTEM OPERATION. INTERFERE WITH SYSTEM OPERATION.
- ALTITUDE: NOT TO EXCEED 7,875 FT. (2400M) ABOVE SEA LEVEL. DO NOT RESTRICT THE AIR INTAKE OR AIR EXHAUST OF THE SYSTEM COMPONENTS.
- ENVIRONMENTAL CONDITIONS LISTED ABOVE MUST BE MAINTAINED AT ALL TIMES INCLUDING FOR EXAMPLE OVERNIGHT, WEEKENDS, AND HOLIDAYS.
- BACKGROUND RADIATION SHOULD BE KEPT TO A MINIMUM. RADIOACTIVE SOURCES MUST BE KEPT IN SHIELDED CONTAINERS AND THE EXAMINATION ROOM SHIELDED FROM EXTERNAL SOURCES.
- DO NOT PLACE PET EQUIPMENT NEAR REGISTERS, WINDOWS OR OTHER COMPONENTS THAT COULD AFFECT TEMPERATURE LEVEL CHANGES IN THE PET EQUIPMENT VICINITY.

MAGNETIC INTERFERENCE SPECIFICATIONS

SCANNER MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 1.0 GAUSS TO GUARANTEE SPECIFIED IMAGING PERFORMANCE.  
 COMPUTER EQUIPMENT MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 10 GAUSS TO GUARANTEE DATA INTEGRITY.  
 DIAGNOSTIC CONSOLE MUST BE LOCATED IN AMBIENT STATIC MAGNETIC FIELDS OF LESS THAN 1 GAUSS TO OBTAIN SPECIFIED GEOMETRIC LINEARITY.

**GE Healthcare**  
 Healthcare Project Implementation - Design Center  
 Milwaukee, WI

SHEET TITLE: EQUIPMENT LAYOUT  
 MODALITY TYPE: OPTIMA PET/CT 560  
 THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF GE HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS. ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS, IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO CURRENT BUILDING CODES AND REGULATIONS. GEHC DOES NOT ACCEPT LIABILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
**12-24f**  
 TYPICAL LAYOUT

PROJECT	REVISION
12-24f	05
DATE:	06 JUN. 16
DRAWN BY:	DMH
CHECKED BY:	REK

REVISION HISTORY:


SHEET  
**A1**

PIM R12  
 RQ - 161174

TYPICAL WALL SUPPORT ELEVATIONS

SCALE: 1/4" = 1'-0"


STRUCTURAL LAYOUT

RECOMMENDED CEILING HEIGHT = 9'-0"

STRUCTURAL SUPPORT METHODS

CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS

ITEM NO.	ITEM DESCRIPTION (* INDICATES EXISTING)
1	FLOOR CONTACT AREA FOR DISCOVERY PET/CT 560 GANTRY AND PATIENT TABLE. SEE DETAIL P5058D ON SHEET S2 FOR MORE INFORMATION.



STRUCTURAL NOTES

- METHODS OF SUPPORT FOR THE STEELWORK THAT WILL PERMIT ATTACHMENT TO STRUCTURAL STEEL OR THROUGH BOLTS IN CONCRETE CONSTRUCTION SHOULD BE FAVORED. DO NOT USE CONCRETE OR MASONRY ANCHORS IN DIRECT TENSION.
- ALL UNITS THAT ARE WALL MOUNTED OR WALL SUPPORTED ARE TO BE PROVIDED WITH SUPPORTS WHERE NECESSARY. WALL SUPPORTS ARE TO BE SUPPLIED AND INSTALLED BY THE CUSTOMER OR HIS CONTRACTORS. SEE PLAN AND DETAIL SHEETS FOR SUGGESTED LOCATIONS AND MOUNTING HOLE LOCATIONS.
- ALL CEILING MOUNTED FIXTURES, AIR VENTS, SPRINKLERS, ETC. TO BE FLUSH MOUNTED, OR SHALL NOT EXTEND MORE THAN 6,35mm (1/4") BELOW THE FINISHED CEILING.
- FLOOR SLABS ON WHICH EQUIPMENT IS TO BE INSTALLED MUST BE LEVEL TO 6,00mm (1/4") IN 3050mm (10'-0").
- DIMENSIONS ARE TO FINISHED SURFACES OF ROOM.
- CUSTOMERS CONTRACTOR MUST PROVIDE ALL PENETRATIONS IN POST TENSION FLOORS.
- CUSTOMERS CONTRACTOR MUST PROVIDE AND INSTALL ANY NON-STANDARD ANCHORING. DOCUMENTS FOR STANDARD ANCHORING METHODS ARE INCLUDED WITH GE EQUIPMENT DRAWINGS FOR GEOGRAPHIC AREAS THAT REQUIRE SUCH DOCUMENTATION.
- CUSTOMERS CONTRACTOR MUST PROVIDE AND INSTALL HARDWARE FOR "THROUGH THE FLOOR" ANCHORING AND/OR ANY BRACING UNDER ACCESS FLOORS. THIS CONTRACTOR MUST ALSO PROVIDE FLOOR DRILLING THAT CANNOT BE COMPLETED BECAUSE OF AN OBSTRUCTION ENCOUNTERED WHILE DRILLING BY THE GE INSTALLER SUCH AS REBAR ETC.
- IT IS THE CUSTOMER'S RESPONSIBILITY TO PERFORM ANY FLOOR OR WALL PENETRATIONS THAT MAY BE REQUIRED. THE CUSTOMER IS ALSO RESPONSIBLE FOR ENSURING THAT NO SUBSURFACE UTILITIES (E.G., ELECTRICAL OR ANY OTHER FORM OF WIRING, CONDUITS, PIPING, DUCT WORK OR STRUCTURAL SUPPORTS (I.E. POST TENSION CABLES OR REBAR)) WILL INTERFERE OR COME IN CONTACT WITH SUBSURFACE PENETRATION OPERATIONS (E.G. DRILLING AND INSTALLATION OF ANCHORS/SCREWS) PERFORMED DURING THE INSTALLATION PROCESS. TO ENSURE WORKER SAFETY, GE INSTALLERS WILL PERFORM SURFACE PENETRATION OPERATIONS ONLY AFTER THE CUSTOMER'S VALIDATION AND COMPLETION OF THE "GE SURFACE PENETRATION PERMIT"

SHEET TITLE: STRUCTURAL LAYOUT  
MODALITY TYPE: OPTIMA PET/CT 560

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO ALL APPLICABLE CODES AND STANDARDS. HOWEVER, THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
12-24f  
TYPICAL LAYOUT

PROJECT	REVISION
12-24f	05

DATE: 06.JUN.16  
DRAWN BY: DMH  
CHECKED BY: REK

REVISION HISTORY:

SHEET


S1

PIM R12  
RQ - 161174

**GE Healthcare**  
Healthcare Project Implementation - Design Center  
Madison, Wisconsin

FLOOR MOUNTING DETAIL: PET/CT 560/560FX/610/710 IQ (16 SLICE) INSTALLATION METHODS P5058D

REV. DATE 10.APR.14



SHEET TITLE: STRUCTURAL DETAILS  
 MODALITY TYPE: OPTIMA PET/CT 560

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE LATEST EDITIONS OF THE NATIONAL BUILDING CODES AND THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
 12-24f  
 TYPICAL LAYOUT

PROJECT	REVISION
12-24f	05
DATE:	06.JUN.16
DRAWN BY:	DMH
CHECKED BY:	REK

REVISION HISTORY:  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

SHEET  
 S2

**GE Healthcare**  
 Healthcare Project Implementation - Design Center  
 Milwaukee, Wisconsin

SCALE: 1/4" = 1'-0"

ELECTRICAL PLAN

RECOMMENDED CEILING HEIGHT = 9'-0"

**ELECTRICAL OUTLET LEGEND**  
CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS. HEIGHT ABOVE FLOOR DETERMINED BY LOCAL CODES UNLESS OTHERWISE SPECIFIED.






- △ DEDICATED TELEPHONE LINES (SEE ELECTRICAL DETAIL ELEC-1 OR ELEC-67)
- ▲ NETWORK OUTLET (SEE ELECTRICAL DETAILS ELEC-83 AND ELEC-84 OR ELEC-87)

JUNCTION POINT NOTES

- ALL JUNCTION BOXES, CONDUIT, DUCT, DUCT DIVIDERS, SWITCHES, CIRCUIT BREAKERS, CABLE TRAY, ETC., ARE TO BE SUPPLIED AND INSTALLED BY CUSTOMER'S ELECTRICAL CONTRACTOR.
- CONDUIT AND DUCT RUNS SHALL HAVE SWEEP RADIUS BENDS
- CONDUITS AND DUCT ABOVE CEILING OR BELOW FINISHED FLOOR MUST BE INSTALLED AS NEAR TO CEILING OR FLOOR AS POSSIBLE TO REDUCE RUN LENGTH.
- CEILING MOUNTED JUNCTION BOXES ILLUSTRATED ON THIS PLAN MUST BE INSTALLED FLUSH WITH FINISHED CEILING.
- ALL DUCTWORK MUST MEET THE FOLLOWING REQUIREMENTS:
  1. DUCTWORK SHALL BE METAL WITH DIVIDERS AND HAVE REMOVABLE, ACCESSIBLE COVERS.
  2. DUCTWORK SHALL BE CERTIFIED/RATED FOR ELECTRICAL POWER PURPOSES.
  3. DUCTWORK SHALL BE ELECTRICALLY AND MECHANICALLY BONDED TOGETHER IN AN APPROVED MANNER.
  4. PVC AS A SUBSTITUTE MUST BE USED IN ACCORDANCE WITH ALL LOCAL AND NATIONAL CODES.
- ALL OPENINGS IN ACCESS FLOORING ARE TO BE CUT OUT AND FINISHED OFF WITH GROMMET MATERIAL BY THE CUSTOMER'S CONTRACTOR.
- GENERAL CONTRACTOR TO INSERT PULL CORDS FOR ALL CABLE RUN CONDUITS BETWEEN THE EQUIPMENT ROOM AND THE OPERATORS CONTROL ROOM.
- 10 FOOT PIGTAILS AT ALL JUNCTION POINTS.
- ALL WIRING MUST BE THHN OR TFFN STRANDED COPPER THERMOPLASTIC 600 VOLT OR EQUIVALENT INSULATION. **ALUMINUM OR SOLID WIRES ARE NOT ALLOWED.**
- GROUNDING IS CRITICAL TO EQUIPMENT FUNCTION AND PATIENT SAFETY. SITE MUST CONFORM TO WIRING SPECIFICATIONS SHOWN ON THIS PLAN.

JUNCTION POINT DESCRIPTIONS

POINT	DESCRIPTION	QTY.	HARDWARE	DETAIL NO., SHT. E3
A1	MAIN DISCONNECT AVAILABLE FROM GEHC CALL 800-279-7925 OR LOCAL GE INSTALLATION PROJECT MGR.	1	90 AMP FUSED DISCONNECT AND MAGNETIC CONTACTOR GEMS CAT. NO. E4502AB 7.50" PUSHBUTTON AND COVER INCLUDED	
CTPT	CT-PET SCANNER	2	2 1/2 IN. DIA. BUSHING & LOCKNUT 3/8 IN. DIA. BUSHING & LOCKNUT	ELEC-25
DLK1	DOOR SWITCH (NEEDED ONLY IF REQUIRED BY STATE/LOCAL CODES)	1	ROOM DOOR INTERLOCK LIMIT SWITCH IN FRAME - NORMALLY OPEN (24V) SINGLE GANG BOX	
OC	OPERATORS CONSOLE	1	12 IN. OF GROMMET MATERIAL FOR A 3 X 3 IN. OPENING IN DUCT COVER	ELEC-5
PDU	POWER DISTRIBUTION UNIT	1	SPLIT COVERPLATE 3 X 3 IN. OPENING IN DUCT COVER 4 80 IN. 90 DEGREE CONNECTOR 6 FT. LENGTH OF 2 1/2 IN. FLEXIBLE METAL CONDUIT 2 SUITABLE CONNECTORS 12 X 16 X 4 IN. BOX 1 6 FT. LENGTH OF 1/2 IN. FLEXIBLE METAL CONDUIT	ELEC-5 ELEC-22
OCOR	OCOR	1	12 IN. OF GROMMET MATERIAL FOR A 3 X 3 IN. OPENING IN DUCT COVER	ELEC-5
SEO	EMERGENCY OFF	1	SINGLE GANG 2 1/2 IN. DEEP FLUSH MOUNTED JUNCTION BOX.	ELEC-16
UPS	UPS CABINET	1	COVERPLATE 1 1/2 IN. DIA. CHASE NIPPLE 1 1/2 X 4 X 4 IN. BOX 1 1/2 IN. DIA. CHASE NIPPLE 1 1/2 IN. DIA. BUSHING & LOCKNUT (IF OPTIONAL 2 IN. CND IS USED, ADD THE FOLLOWING) 4 X 4 X 4 IN. BOX 1 COVERPLATE	ELEC-8
WL	WARNING LIGHT	1	COVERPLATE SINGLE GANG BOX 1 X-RAY ON - INCANDESCENT LIGHT FIXTURE - DO NOT USE FLUORESCENT FIXTURES. E4500RL WARNING LIGHT 24V CONTROL DR EQUIVALENT.	
WLC	WARNING LIGHT CONTROLLER AVAILABLE FROM GEHC CALL 800-279-7925 OR LOCAL GE INSTALLATION PROJECT MGR.	1	E4500AM WARNING LIGHT CONTROL DR EQUIVALENT MAX 24V CONTROLLER	ELEC-17



**FEEDER TABLE - PET/CT 560/560FX/600/690 ELITE/610,710,Q (16 SLICE)**

○ CALCULATIONS BASED UPON NOMINAL VOLTAGE, WIRE SIZE IN AWG.  
○ RECOMMENDED FEEDER SIZES FROM DISTRIBUTION TRANS. TO POWER DISTRIBUTION UNIT.  
○ THE GROUNDING CONDUCTOR (3) WILL BE A 1/0 MINIMUM. THIS GROUND WILL RUN FROM THE EQUIPMENT BACK TO THE POWER SOURCE/MAIN GROUNDING POINT AND ALWAYS TRAVEL IN THE SAME CONDUIT WITH THE FEEDERS AND NEUTRAL.  
○ NEUTRAL MUST BE TERMINATED PRIOR TO OR INSIDE THE MAIN DISCONNECT PANEL AND NOT BROUGHT INTO THE POWER DISTRIBUTION UNIT.  
○ FOR A FULL SYSTEM UPS REFER TO ELECTRICAL DETAILS FOR UPS FEEDER WIRES.

RUN LENGTH IN FEET	POWER SUPPLY VOLTAGE									
	342-418 380	360-440 400	378-462 420	396-484 440	414-506 460	432-528 480	FEEDER	GROUND		
50	2	(1/0)	2	(1/0)	3	(1/0)	3	(1/0)	3	(1/0)
100	2	(1/0)	2	(1/0)	3	(1/0)	3	(1/0)	3	(1/0)
150	2	(1/0)	2	(1/0)	3	(1/0)	3	(1/0)	3	(1/0)
200	2	(1/0)	2	(1/0)	3	(1/0)	3	(1/0)	3	(1/0)
250	1	(1/0)	1	(1/0)	2	(1/0)	2	(1/0)	2	(1/0)
300	1/0	(2/0)	1/0	(1/0)	1	(1/0)	1	(1/0)	2	(1/0)
350	2/0	(2/0)	1/0	(2/0)	1/0	(1/0)	1	(1/0)	1	(1/0)
400	2/0	(2/0)	2/0	(2/0)	1/0	(1/0)	1/0	(1/0)	1	(1/0)

(REV. DATE 25.APR.14)

**ADDITIONAL CONDUIT RUNS FOR ALL PET/CT 560, 600, 610 690, 710, VCT, STE, ST & IQ COLUMBIA SYSTEMS**

**CONDUITS REQUIRED FOR BASE SYSTEM (CONDUITS ARE LOCATED ABOVE CEILING)**

TO	FROM	CONDUIT SIZE
WL	TO WLC	ONE 1/2" CND.
WLC	TO PDU	ONE 1/2" CND.
PDU	TO A1	ONE CND. AS REQ'D
A1	TO SEO	ONE 1/2" CND.
A1	TO FEEDER	ONE CND. AS REQ'D
WLC	TO 120-V 1Ø POWER	CND. AS REQ'D
DLK1	TO PDU	ONE 1/2" CND.

NOTE: SEE E2 PAGE FOR MAXIMUM RUN LENGTHS

**CONDUITS REQUIRED FOR UPS (CONDUITS ARE LOCATED ABOVE CEILING)**

TO	FROM	CONDUIT SIZE
UPS	TO A1	ONE 1 1/4" CND.
UPS	TO PM	ONE 2" CND. (OPTIONAL) RUN DIRECT AS POSSIBLE. 12' MAX CABLE LENGTH

REV DATE: 23.MAY.14

**CONTRACTOR SUPPLIED AND INSTALLED WIRING**  
ELECTRICAL CONTRACTOR SHALL RING OUT, TAG AND TERMINATE ALL WIRES AT BOTH ENDS.

WIRE RUN, FROM - TO	QUANTITY, WIRE SIZE/COLOR
A1 > SEO	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
480-V > A1	3 BLACK, 1 WHITE, 1 GREEN - REFER TO FEEDER TABLE
A1 > PDU	3-BLACK, 1 GREEN - REFER TO FEEDER TABLE
WLC > PDU	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
WLC > 1 PHASE	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN
WL > WLC	2-ND. 14 BLACK, 1-ND. 14 RED, 1-ND. 14 WHITE
PDU > DLK1	1-ND. 14 BLACK, 1-ND. 14 WHITE, 1-ND. 14 GREEN

**GE Healthcare**  
Healthcare Project Implementation - Design Center  
Minneapolis, MN

SHEET TITLE: ELECTRICAL LAYOUT  
MODALITY TYPE: OPTIMA PET/CT 560

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS. ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS, IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO ALL APPLICABLE CODES AND REGULATIONS. THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.


PROJECT TITLE: 12-24f  
TYPICAL LAYOUT

PROJECT: 12-24f  
REVISION: 05  
DATE: 06.JUN.16  
DRAWN BY: DMH  
CHECKED BY: REK

REVISION HISTORY:

SHEET  
E1

INTERCONNECT DIAGRAM



POWER SPECIFICATIONS

PET/CT 560/560FX, 610/710, IQ (8,16 SLICE)

(REV DATE: 25APR.14)

VOLTAGE PRIMARY SOURCE IS REQUIRED FOR ALL INSTALLATIONS. RANGE OF LINE VOLTAGES: NOMINAL LINE VOLTAGE OF 380 TO 480, 3 PHASE, 50 OR 60 HZ.  
REQUIRED POWER SUPPLY: WYE CONNECTED  
MAXIMUM DAILY VOLTAGE VARIATION MUST FALL WITHIN ONE OF THE RANGES IN TABLE A.

TABLE A ALLOWABLE INPUT VOLTAGES/CURRENT DEMAND

NOMINAL VOLTAGE	ABSOLUTE RANGE	CURRENT (AMPS)		MINIMUM STANDARD OVERCURRENT PROTECTION
		MOMENTARY	CONTINUOUS	
380	342-418	137	30	110-A
400	360-440	130	29	110-A
420	378-462	124	27	100-A
440	396-484	118	26	100-A
460	414-506	113	25	90-A
<b>480</b>	<b>434-528</b>	<b>108</b>	<b>24</b>	<b>90-A</b>

(ALL CALCULATIONS BASED UPON NOMINAL VOLTAGE)

PHASE-TO-PHASE VOLTAGES MUST BE WITHIN +2 PERCENT OF THE LOWEST PHASE-TO-PHASE VOLTAGE. MAXIMUM ALLOWABLE TRANSIENT VOLTAGE EXCURSIONS ARE 2.5 PERCENT OF RATED LINE VOLTAGE AT A MAXIMUM DURATION OF 1 CYCLE AND FREQUENCY OF 10 TIMES PER HOUR.

VOLTAGE TRANSIENT OR IMPULSE ON THE INCOMING POWER MUST BE HELD TO A MINIMUM. TRANSIENTS CAUSED BY LIGHTNING, SURGES, LOAD SWITCHING, STATIC ELECTRICITY ETC. CAN CAUSE SCAN ABORTS OR IN EXTREME INSTANCES, COMPONENT FAILURE IN THE COMPUTER SUBSYSTEM.

POWER DEMAND

CONTINUOUS POWER DEMAND = 30 KVA (MAX DEMAND = 90 KVA)

TABLE B MAXIMUM MOMENTARY POWER DEMAND.

DEMAND	D600\690 ELITE
kVa *	90
POWER FACTOR AT	0.85

\* DEMAND INCLUDES POWER FOR ENTIRE CT SYSTEM. LINE VOLTAGE REGULATION AT MAXIMUM POWER DEMAND MUST BE LESS THAN OR EQUAL TO 6 PERCENT.

DISTRIBUTION TRANSFORMER

FOR A SINGLE UNIT INSTALLATION, THE MINIMUM TRANSFORMER SIZE IS 112.5 KVA. GE DOES NOT RECOMMEND USING A REGULATION DEVICE.

NOTE: DO NOT USE AN EXISTING DISTRIBUTION TRANSFORMER TO POWER A SYSTEM IF OTHER X-RAY EQUIPMENT USING RAPID FILM CHANGERS, IS CONNECTED TO THE EXISTING TRANSFORMER.

ELECTRICAL NOTES

- NOTE 1: ALL WIRES SPECIFIED SHALL BE COPPER STRANDED, FLEXIBLE, THERMO-PLASTIC, COLOR CODED, CUT 10 FOOT LONG AT OUTLET BOXES, DUCT TERMINATION POINTS OR STUBBED CONDUIT ENDS. ALL CONDUCTORS, POWER, SIGNAL AND GROUND, MUST BE RUN IN A CONDUIT OR DUCT SYSTEM. ELECTRICAL CONTRACTOR SHALL RING OUT AND TAG ALL WIRES AT BOTH ENDS. WIRE RUNS MUST BE CONTINUOUS COPPER STRANDED AND FREE FROM SPLICES. **ALUMINUM OR SOLID WIRES ARE NOT ALLOWED.**
- NOTE 2: WIRE SIZES GIVEN ARE FOR USE OF EQUIPMENT. LARGER SIZES MAY BE REQUIRED BY LOCAL CODES.
- NOTE 3: IT IS RECOMMENDED THAT ALL WIRES BE COLOR CODED, AS REQUIRED IN ACCORDANCE WITH NATIONAL AND LOCAL ELECTRICAL CODES.
- NOTE 4: CONDUIT SIZES SHALL BE VERIFIED BY THE ARCHITECT, ELECTRICAL ENGINEER OR CONTRACTOR, IN ACCORDANCE WITH LOCAL OR NATIONAL CODES.
- NOTE 5: CONVENIENCE OUTLETS ARE NOT ILLUSTRATED. THEIR NUMBER AND LOCATION ARE TO BE SPECIFIED BY OTHERS. LOCATE AT LEAST ONE CONVENIENCE OUTLET CLOSE TO THE SYSTEM CONTROL, THE POWER DISTRIBUTION UNIT AND ONE ON EACH WALL OF THE PROCEDURE ROOM. USE HOSPITAL APPROVED OUTLET OR EQUIVALENT.
- NOTE 6: GENERAL ROOM ILLUMINATION IS NOT ILLUSTRATED. CAUTION SHOULD BE TAKEN TO AVOID EXCESSIVE HEAT FROM OVERHEAD SPOTLIGHTS. DAMAGE CAN OCCUR TO CEILING MOUNTING COMPONENTS AND WIRING IF HIGH WATTAGE BULBS ARE USED. RECOMMEND LOW WATTAGE BULBS NO HIGHER THAN 75 WATTS AND USE DIMMER CONTROLS (EXCEPT MR). DO NOT MOUNT LIGHTS DIRECTLY ABOVE AREAS WHERE CEILING MOUNTED ACCESSORIES WILL BE PARKED.
- NOTE 7: **ROUTING OF CABLE, DUCTWORK, CONDUITS, ETC., MUST RUN DIRECT AS POSSIBLE OTHERWISE MAY RESULT IN THE NEED FOR GREATER THAN STANDARD CABLE LENGTHS (REFER TO THE INTERCONNECTION DIAGRAM FOR MAXIMUM USABLE LENGTHS POINT TO POINT).**
- NOTE 8: CONDUIT TURNS TO HAVE LARGE, SWEEPING BENDS WITH MINIMUM RADIUS IN ACCORDANCE WITH NATIONAL AND LOCAL ELECTRICAL CODES.
- NOTE 9: A SPECIAL GROUNDING SYSTEM IS REQUIRED IN ALL PROCEDURE ROOMS BY SOME NATIONAL AND LOCAL CODES. IT IS RECOMMENDED IN AREAS WHERE PATIENTS MIGHT BE EXAMINED OR TREATED UNDER PRESENT, FUTURE, OR EMERGENCY CONDITIONS. CONSULT THE GOVERNING ELECTRICAL CODE AND CONFER WITH APPROPRIATE CUSTOMER ADMINISTRATIVE PERSONNEL TO DETERMINE THE AREAS REQUIRING THIS TYPE OF GROUNDING SYSTEM.
- NOTE 10: THE MAXIMUM POINT TO POINT DISTANCES ILLUSTRATED ON THIS DRAWING MUST NOT BE EXCEEDED.
- NOTE 11: PHYSICAL CONNECTION OF PRIMARY POWER TO GE EQUIPMENT IS TO BE MADE BY CUSTOMERS ELECTRICAL CONTRACTOR WITH THE SUPERVISION OF A GE REPRESENTATIVE. THE GE REPRESENTATIVE WOULD BE REQUIRED TO IDENTIFY THE PHYSICAL CONNECTION LOCATION, AND INSURE PROPER HANDLING OF GE EQUIPMENT.
- NOTE 12: GEHC CONDUCTS POWER AUDITS TO VERIFY QUALITY OF POWER BEING DELIVERED TO THE SYSTEM. THE CUSTOMER'S ELECTRICAL CONTRACTOR IS REQUIRED TO BE AVAILABLE TO SUPPORT THIS ACTIVITY.

DIAGRAM KEY

- CUSTOMER/CONTRACTOR SUPPLIED WIRING. ROUTE IN ADEQUATE CONDUIT OR RACEWAY.
- GE FURNISHED CABLE RUNS. ROUTE IN EMPTY CONDUIT OR RACEWAY.
- 59' [18M] MAXIMUM RUN LENGTH BETWEEN JUNCTION POINTS. Feet, [Meters]

THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED

GE Healthcare



Healthcare Project Implementation - Design Center  
Wisconsin

SHEET TITLE: ELECTRICAL SPECIFICATIONS  
MODALITY TYPE: OPTIMA PET/CT 560

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS. ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE LATEST APPLICABLE CODES AND STANDARDS. THE COMPANY CANNOT ACCEPT LIABILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
12-24f  
TYPICAL LAYOUT

PROJECT	REVISION
12-24f	05

DATE: 06.JUN.16  
DRAWN BY: DMH  
CHECKED BY: REK

REVISION HISTORY:  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

SHEET  
E2

PIM R12  
RQ - 161174

### ELECTRICAL DETAIL X-RAY WARNING LIGHT & ROOM LIGHT CONTROL PANEL

**ELEC-17**  
REV. DATE: 10.APR.13

**E4502SS**  
X-RAY ROOM WARNING LIGHT / ROOM LIGHTING CONTROL PANEL

TO GE X-RAY ON SIGNAL: MAXIMUM 24-VAC  
TO GE ROOM LIGHT SIGNAL: MAXIMUM 24-VAC

120-VAC 10A MAXIMUM  
0-VAC  
10A MAX  
0-VAC  
10A MAX

**E4502RL**  
X-RAY ROOM WARNING LIGHT CONTROL PANEL

TO GE X-RAY ON SIGNAL: MAXIMUM 24-VAC

120-VAC 10A MAXIMUM  
0-VAC

CONTROL PANEL CAN BE LOCATED ABOVE THE CEILING NEAR THE WARNING LIGHT  
UNLESS SPECIFIED ON SHEET A1 AS BEING INCLUDED ON EQUIPMENT ORDER,  
ALL ITEMS ILLUSTRATED ARE TO BE FURNISHED AND INSTALLED BY CUSTOMER'S CONTRACTOR

### ELECTRICAL DETAIL HORIZONTAL WALL DUCT (TYPICAL)

**ELEC-5**  
REV. DATE: 03/19/04

REFER TO CHART FOR MINIMUM DIVIDER REQUIREMENT  
LOCAL CODES MAY REQUIRE ADDITIONAL DIVIDERS

DUCT WIDTH	MINIMUM DIVIDERS REQUIRED
24" [610mm]	2
18" [457mm]	2
10" [254mm]	2
6" [152mm]	1
4" [102mm]	1

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL VERTICAL WALL DUCT (TYPICAL)

**ELEC-6**  
REV. DATE: 03/19/04

REFER TO CHART FOR MINIMUM DIVIDER REQUIREMENT  
LOCAL CODES MAY REQUIRE ADDITIONAL DIVIDERS

DUCT WIDTH	MINIMUM DIVIDERS REQUIRED
24" [610mm]	2
18" [457mm]	2
10" [254mm]	2
6" [152mm]	1
4" [102mm]	1

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL BOX WITH SPLIT COVERPLATE (TYPICAL)

**ELEC-22**  
REV. DATE: 10/13/94

OUTLET BOX  
SPLIT COVERPLATE  
FLEXIBLE METAL CONDUIT

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL FLUSH FLOOR DUCT (TYPICAL)

**ELEC-25**  
REV. DATE: 4/01/04

FINISHED FLOOR  
REMOVABLE COVER  
HARDWARE

REFER TO CHART FOR MINIMUM DIVIDER REQUIREMENT  
LOCAL CODES MAY REQUIRE ADDITIONAL DIVIDERS

DUCT WIDTH	MINIMUM DIVIDERS REQUIRED
24" [610mm]	2
18" [457mm]	2
10" [254mm]	2
6" [152mm]	1
4" [102mm]	1

12" TRENCH DUCT: A = 10", B = 12"  
18" TRENCH DUCT: A = 18", B = 20"

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL INSITE CONNECTION (TYPICAL)

**ELEC-1**  
REV. DATE: 04/24/02

ONE OF THE FOLLOWING TWO SELECTIONS MUST BE INSTALLED AT THE LOCATION SHOWN ON THE ELECTRICAL PLAN (SHEET E1) FOR GE INSITE CONNECTION BASED UPON SYSTEM CONFIGURATION.

A) ONE INTERNET ACCESSIBLE VIRTUAL PRIVATE NETWORK (VPN) CONNECTION WITH A STATIC IP ADDRESS, AND ONE TELEPHONE LINE - DEDICATED-DIRECT-DIALING, VOICE GRADE.  
OR  
B) TWO TELEPHONE LINES - ONE DEDICATED DIRECT-DISTANCE-DIALING, VOICE GRADE AND ONE A DEDICATED DATA LINE.

FINISHED CEILING  
FINISHED FLOOR  
SINGLE GANG J.B.  
1" CONDUIT FROM J.B. TO ABOVE FINISHED CEILING.  
TO BE DETERMINED

COVERPLATE WITH TWO TELEPHONE RECEPTACLES OR ONE TELEPHONE RECEPTACLE AND ONE NETWORK RECEPTACLE

ALL ITEMS ILLUSTRATED ARE TO BE FURNISHED AND INSTALLED BY CUSTOMER OR THEIR CONTRACTOR.

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL BOX WITH COVERPLATE AND NETWORK JACK

**ELEC-83**  
REV. DATE: 10/06/98

BOX  
NETWORK JACK  
COVERPLATE

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL NETWORK CONNECTION (TYPICAL)

**ELEC-84**  
REV. DATE: 03/06/04

FOR NUCLEAR SYSTEMS A DIRECT NETWORK CONNECTION IS TO BE MADE BETWEEN THE SYSTEM AND THE REVIEW WORKSTATION.

LOCAL AREA NETWORK  
FINISHED CEILING  
FINISHED FLOOR  
SINGLE GANG J.B.  
1/2" CONDUIT FROM J.B. TO ABOVE FINISHED CEILING.  
TO BE DETERMINED

COVERPLATE WITH NETWORK RECEPTACLE

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL BOX WITH COVERPLATE (TYPICAL)

**ELEC-8**  
REV. DATE: 09/30/94

OUTLET BOX  
HARDWARE

DETAIL NOT TO SCALE

### ELECTRICAL DETAIL EMERGENCY OFF BUTTON

**ELEC-16**  
REV. DATE: 05/14/09

PLAN VIEW  
FRONT VIEW  
SIDE VIEW  
SINGLE GANG BOX SUPPLIED BY CONTRACTOR  
PLATE & OFF BUTTON  
2 1/2" [64mm]

DETAIL NOT TO SCALE

**GE Healthcare**  
Healthcare Project Implementation - Design Center  
Manufacture

SHEET TITLE: ELECTRICAL DETAILS  
MODALITY TYPE: OPTIMA PET/CT 560

THIS PLAN IS SUBMITTED TO SUBMIT LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL FIRE ALARM AND SIGNALING CODE (NFPA 72). THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
**12-24f**  
TYPICAL LAYOUT




PROJECT	REVISION
12-24f	05

DATE: 06.JUN.16  
DRAWN BY: DMH  
CHECKED BY: REK

REVISION HISTORY:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

SHEET  
**E3**



### EQUIPMENT DETAIL EQUIPMENT SHIPPING DETAIL


B5060A  
REV. DATE: 08.JAN.15

CONFIGURATION	LENGTH - IN. [MM]	WIDTH - IN. [MM]	HEIGHT - IN. [MM]	WEIGHT - lb [kg]
64 SLICE CT GANTRY, DOLLIES ON, SIDE RAILS ON	114 [2896]	51 [1295]	77 [1955]	4260 [1932]
16 SLICE CT GANTRY, DOLLIES ON, SIDE RAILS ON	111 [2810]	51 [1290]	79 [2000]	4360 [1982]
PET SOURCE RING AND TRAILER W/DOLLIES	96 [2438]	41.5 [1054]	43 [1092]	1340 [608]
PET IMAGE RING DOLLIES ON, SIDE BRACES ON	110 [2794]	44 [1118]	74 [1880]	2820 [1282]
PET IMAGE RING WITHOUT DOLLIES	76 [1931]	28 [720]	72 [1819]	2110 [954]
PET RETRACTOR & BASE ASSEMBLY	96 [2438]	41.5 [1054]	39 [990]	1495 [678]
Q.CORE ON SKID	34 [864]	25 [635]	42 [1067]	87 [192]
POWER DISTRIBUTION UNIT W/CARDBOARD PACKAGING	30 [762]	23 [584]	43 [1092]	910 [413]
CONSOLE ON SKID	34 [864]	25 [635]	42 [1067]	192 [87]
TABLE - BLUE DOLLIES ON	58 [3836]	34 [864]	55.5 [1410]	1241 [2736]
TABLE - BLUE DOLLIES OFF RED CASTORS ON	120 [3048]	40 [1016]	55.5 [1410]	1295 [2856]
TABLE TILTING	98-115 [2489-2921]	38 [965]	70-80 [1778-2032]	2530 [1147]

### EQUIPMENT DETAIL EQUIPMENT SHIPPING DETAIL

B5060C  
REV. DATE: 10.APR.14






CONFIGURATION	LENGTH - IN. [MM]	WIDTH - IN. [MM]	HEIGHT - IN. [MM]	WEIGHT - lb [kg]
SKID WITH Q.CORE	34 [864]	25 [635]	42 [1067]	192 [87]
SKID WITH CONSOLE & COMPONENTS	34 [864]	25 [635]	42 [1067]	192 [87]
ANNULUS PHANTOM SAFE	36 [914]	36 [914]	36 [914]	480 [217]



### EQUIPMENT DETAIL STORAGE CABINET CHART

B60900  
REV. DATE: 09.JUL.12

ITEM	SIZE	WEIGHT
STORAGE CABINET	46 X 91 X 107 CM (18" D X 36" W X 42" H)	45.3 KG (100 LB) (APPROXIMATELY)
QA PHANTOM (WATER FILLED)	23 X 15 CM (9" X 6")	4.5 KG (10 LB)
PET PHANTOM (VCQ)	45 X 35 X 20 CM (18" X 14" X 8")	0.9 KG (2 LB)
PHANTOM HOLDER	25 X 25 CM (10" X 10")	9.1 KG (20 LB)
FE DOCUMENTS & CD/DVD		
35 CM POLY (CIRCLE)	35 X 8 CM (14" X 3")	6.8 KG (15 LB)
48 CM POLY (CIRCLE)	48 X 8 CM (19" X 3")	11.3 KG (25 LB)
STOOL	48 X 48 CM (19H X 19H)	1 KG (2 LB)
BLUE TOTE	81 X 51 X 32 CM (30" X 20F X 17")	2 KG (4 LB)
INSTALL SUPPORT KIT (BOX)	30 X 30 X 38 CM (12" X 12" X 15")	9.1 KG (20 LB)
TUBE HOIST KIT	77 X 8 CM AND 38 X 15 CM (30" X 3" AND 15" X 6")	13.6 KG (30 LB)
BALANCE WEIGHT KIT	(2 BOXES)	33 KG (73 LB)
SPATIAL RESOLUTION PHANTOM	18 X 15 X 8 CM (7" X 6" X 3")	-




PIM R12  
 RQ - 161174



EQUIPMENT DETAIL  
OPERATORS CONSOLE – COMPUTER


B81-42  
REV. DATE: 11.JUL.12

- INDICATES CENTER OF GRAVITY
- NOTE: DETAIL NOT TO SCALE
- UNITS IN INCHES BRACKETED DIMENSIONS EQUAL [MM]



EQUIPMENT DETAIL  
UPS SYSTEM (CAT. NO. B7864PZ/P5064PS/E4502F)

B7864PZ  
REV. DATE: 26.AUG.15



**GE Healthcare**  
Healthcare Project Implementation – Design Center  
Milwaukee, Wisconsin

SHEET TITLE: EQUIPMENT DETAILS  
MODALITY TYPE: OPTIMA PET/CT 560

THIS PLAN IS SUBMITTED TO SUGGEST LOCATION OF HEALTHCARE EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMENTS. IN PREPARING THIS PLAN, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE, THE NATIONAL PLUMBING CODE, THE NATIONAL MECHANICAL CODE, AND THE COMPANY CANNOT ACCEPT RESPONSIBILITY FOR ANY DAMAGES RESULTING THEREFROM.

PROJECT TITLE:  
**12-24f**  
**TYPICAL LAYOUT**

PROJECT	REVISION
12-24f	05
DATE:	06.JUN.16
DRAWN BY:	DMH
CHECKED BY:	REK

REVISION HISTORY:  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

SHEET  
**D2**

PIM R12  
RQ - 161174